



TITLE:

The Definitive Guide to Delay Analysis: Methodologies, Protocols, and Forensic Schedule Techniques

Athor:

**Behzad Mousavi, MSc in Industrial Engineering
Planning & Project Control Specialist**

Introduction: The Anatomy of Project Delays

In the complex ecosystem of industrial projects, construction, and engineering, time is not merely a metric—it is a currency. When a project deviates from its baseline schedule, the financial and contractual repercussions can be severe. Liquidated damages, prolonged overheads, and strained stakeholder relationships are just the tip of the iceberg. This is where Delay Analysis becomes the critical intersection between project management, forensic accounting, and contract law.

Delay analysis is the systematic process of investigating, quantifying, and assigning responsibility for delays in a project schedule

www.smithcurrie.com

. It is the engine that drives Extension of Time (EOT) claims and financial compensation. However, it is also one of the most contentious areas of project management. Disputes rarely arise because a delay occurred; they arise because parties disagree on why it occurred, who caused it, and how much time it actually added to the completion date.

This comprehensive guide delves into the forensic methodologies used to dissect project delays. We will explore the gold-standard techniques endorsed by the Society of Construction Law (SCL) and the Association for the Advancement of Cost Engineering (AACE), decode the mystery of concurrent delays, and provide a strategic framework for preparing defensible delay claims.

The Foundation: Why Delay Analysis Matters

Before diving into the mechanics, it is essential to understand the objectives of delay analysis. It is not simply about blaming a party; it is about establishing entitlement under the contract.

1. Extension of Time (EOT)

Most standard contracts (FIDIC, NEC, JCT) allow the contractor to request an extension of the completion date if delays are caused by "Employer Risks" (e.g., late design approvals, changes in law). Delay analysis provides the quantum of days required for this extension, relieving the contractor from liquidated damages

www.scl.org.uk

.

2. Financial Compensation (Prolongation Costs)

If a delay is "compensable" (caused by the client), the contractor is entitled to recover time-related costs (site overheads, equipment rental). Delay analysis links the specific delay event to the specific cost incurred.

3. Preserving Rights

Many contracts have strict "time-bar" clauses requiring notice of delay within a specific window (e.g., 28 days). Robust delay analysis ensures that notices are substantiated with data, preventing claims from being rejected on procedural grounds.

The Golden Rules: The SCL Delay and Disruption Protocol

Any discussion on delay analysis must begin with the Society of Construction Law (SCL) Delay and Disruption Protocol. First published in 2002 and updated in 2017, this document is widely regarded as the global benchmark for best practices in delay analysis

www.scl.org.uk

.

The Protocol identifies 22 Core Principles that govern how delays should be managed and analyzed

www.linkedin.com

. While we cannot cover all 22 here, several are fundamental to any forensic analysis:

Core Principle 1 (Purpose of EOT): The purpose of an EOT is to relieve the contractor from liability for liquidated damages, not necessarily to fix a new completion date for the employer's convenience.

Core Principle 4 (Float): Float is generally available to the project, not the contractor or employer exclusively. If a delay consumes float, it may not entitle the contractor to an EOT unless the contract states otherwise

sccsinternational.org

.

Core Principle 10 (Methodology): The Protocol recommends Time Impact Analysis (TIA) as the preferred method for prospective analysis and Windows Analysis for retrospective analysis

aven-ai.com

.

Core Principle 14 (Concurrent Delay): If two delays occur simultaneously—one compensable and one non-compensable—the contractor is generally entitled to an EOT but not additional costs

www.long-intl.com

.

Understanding these principles is crucial because courts and arbitrators often rely on the SCL Protocol to determine if a delay analysis methodology is acceptable

www.ibanet.org

.

Forensic Methodologies: The Toolkit of the Analyst

There is no "one size fits all" approach to delay analysis. The choice of method depends on the availability of records, the complexity of the project, and the requirements of the contract. The SCL Protocol and AACE International classify these methods into two main categories: Observational and Modeled.

Category A: Observational Methods (Retrospective)

These methods look at what actually happened (As-Built) and compare it to what was planned. They are fact-based but can be criticized for ignoring the dynamic nature of scheduling logic.

1. As-Planned vs. As-Built (APAB)

This is the simplest and oldest form of delay analysis. It involves comparing the baseline schedule (As-Planned) with the final actual schedule (As-Built) to identify variances

www.interface-consulting.com

.

How it works: You line up the two schedules side-by-side. If Task A was planned for 10 days but took 20 days, you identify a 10-day delay. You then investigate the cause.

Pros: Easy to understand; requires minimal software sophistication.

Cons: It is highly susceptible to criticism. It ignores the fact that the critical path may have shifted during the project. It assumes the original plan was perfect and the final outcome is the only reality, failing to account for dynamic logic changes

www.deutschkerrigan.com

. Courts often view APAB with skepticism if used for complex claims

www.deutschkerrigan.com

.

2. Windows Analysis (Time Slice / Contemporaneous Period Analysis)

This is widely considered the most robust retrospective method. It breaks the project timeline into "windows" or periods (usually defined by monthly schedule updates) and analyzes the critical path within each window

www.interface-consulting.com

.

How it works:

Window 1 (Month 1): Compare Baseline vs. Update 1. Identify delays.

Window 2 (Month 2): Compare Update 1 vs. Update 2. Identify new delays.

Repeat until project end.

Why it's powerful: It captures the "dynamic" nature of the critical path. If the critical path shifted from "Foundation" to "Steel Erection" in Month 3, Windows Analysis captures this shift. It relies on contemporaneous records (updates submitted during the project), which makes it highly defensible in court

mlrprojectmanagement.com

.

Variations:

Observational Windows: Simply observing the change in critical path between updates.

Modeled Windows (Retrospective TIA): Inserting delay events into the schedule update for that specific window to model their impact

www.linkedin.com

.

Category B: Modeled Methods (Prospective & Retrospective)

These methods involve inserting "what-if" scenarios into a schedule model to predict or measure impact.

3. Time Impact Analysis (TIA)

TIA is the "Gold Standard" recommended by the SCL Protocol for analyzing delays as they happen (prospective) or shortly after

www.interface-consulting.com

. It is the most technically rigorous method.

How it works:

Take the accepted schedule update immediately prior to the delay event.

Create a copy (the "Impacted Schedule").

Insert a "fragnet" (a fragment network of new activities representing the delay event) into the schedule.

Recalculate the schedule.

Compare the completion date of the Impacted Schedule vs. the Unimpacted Schedule. The difference is the delay impact

www.linkedin.com

.

Pros: It isolates the specific impact of a single event on the critical path at a specific point in time. It is transparent and logical.

Cons: It requires a high-quality, logic-driven schedule. If the baseline schedule is flawed, the TIA results will be flawed ("Garbage In, Garbage Out").

4. Collapsed As-Built (But-For Analysis)

This is a retrospective modeling technique. It starts with the As-Built schedule and removes the delays caused by the opposing party to see when the project would have finished "but for" those delays

www.hka.com

.

How it works: You take the actual history and delete the client-caused delays. The remaining duration is the contractor's liability.

Pros: Useful when there is no reliable baseline schedule.

Cons: Highly subjective. Removing activities can alter the logic of the entire schedule in unrealistic ways. It is often challenged by opposing experts.

The Nightmare Scenario: Concurrent Delays

Perhaps the most complex aspect of delay analysis is **Concurrency**. A concurrent delay occurs when two or more independent delays overlap in time, affecting the project completion date

www.long-intl.com

.

The Classic Example

Imagine a project where:

Event A (Client Risk): The client issues a late design change for the HVAC system (Compensable Delay).

Event B (Contractor Risk): The contractor's concrete supplier goes on strike (Non-Compensable Delay).

Both events happen during the same month, and both affect the Critical Path. The project is delayed by 30 days.

How to Analyze Concurrency

The treatment of concurrent delays varies by jurisdiction and contract, but the general principles are:

True Concurrency: Both delays must affect the same critical path at the same time. If one delay affects the critical path and the other affects a non-critical path, they are not truly concurrent regarding the completion date

cpmteam.com

.

Entitlement:

Time: Under the SCL Protocol and many common law jurisdictions, if a concurrent delay exists, the contractor is usually entitled to an Extension of Time (EOT) for the full period. The logic is that the project would have been delayed anyway due to the client's risk, so the contractor shouldn't pay damages

www.long-intl.com

.

Money: However, the contractor is typically not entitled to prolongation costs for the concurrent period. Since the contractor was also delayed by their own fault (the strike), they cannot claim that the client's delay caused the additional cost. The costs are essentially apportioned or borne by the contractor

www.linkedin.com

.

Apportionment

Some contracts (and civil law jurisdictions) allow for apportionment—splitting the responsibility (e.g., 50/50). However, in common law (UK, US, Australia), the "Malmaison Approach" often prevails: if a relevant event (client risk) is a concurrent cause, the contractor gets time but no money

www.dwt.com

.

Step-by-Step: Conducting a Robust Delay Analysis

Whether you are a contractor preparing a claim or an employer's representative defending against one, the process follows a logical sequence.

Step 1: Data Collection and Validation

Forensic analysis is only as good as the data. You need:

The Baseline Schedule: The approved plan.

Schedule Updates: Monthly progress updates (crucial for Windows Analysis).

As-Built Records: Daily diaries, progress photos, inspection requests, transmittals.

Correspondence: Emails and letters notifying delays.

Tip: Validate the data. Does the As-Built schedule match the daily diaries? If the schedule says "Concrete Poured" on June 1st, but the diary says "Rainy day, no work," your data is corrupted.

Step 2: Identify the Critical Path

You cannot analyze delay without understanding the Critical Path Method (CPM). A delay to a non-critical activity (one with Float) does not delay the project completion date unless it consumes all available float

sccsinternational.org

.

Action: Trace the longest path through the network for each period of the project.

Step 3: Select the Methodology

Prospective (During the project): Use Time Impact Analysis (TIA). Submit it with your EOT application.

Retrospective (After the project): Use Windows Analysis. It is the most defensible method for looking back at a complex history

www.interface-consulting.com

.

No Updates Available: If the contractor failed to submit monthly updates, you may be forced to use As-Planned vs. As-Built or Collapsed As-Built, though these are weaker

constructionfront.com

.

Step 4: Model the Delay (The Fragnet)

For TIA or Modeled Windows, you must build a "Fragnet" (Fragment Network).

Example: A delay due to "Late Approval of Steel Drawings."

Fragnet Activities:

Submit Drawings (Actual Date).

Review Period (Contractual 14 days).

Approval Received (Actual Date).

Impact: Link "Approval Received" to the start of "Fabrication."

Insert this fragment into the schedule at the correct date and recalculate

www.linkedin.com

.

Step 5: Quantify and Categorize

Categorize every day of delay:

Excusable Compensable: Client fault (e.g., Late access). -> Get Time + Money.

Excusable Non-Compensable: Neutral events (e.g., Force Majeure, Weather). -> Get Time only.

Non-Excusable: Contractor fault (e.g., Low productivity). -> No Time, No Money (Pay Damages).

Step 6: Report Writing

The report is the product. It must tell a story.

Executive Summary: For the non-technical decision-makers.

Factual Narrative: Chronological story of what happened, backed by references (e.g., "Letter Ref 123 dated...").

Technical Analysis: Explanation of the CPM, the methodology used, and the results.

Appendices: The schedule files, histograms, and detailed logs.

Common Pitfalls and How to Avoid Them

Even experienced analysts fall into traps that can destroy a claim.

1. The "Global Claim"

A global claim asserts that "the project was delayed by 100 days due to a multitude of events, therefore we want 100 days." It fails to link specific events to specific impacts.

Avoidance: Always use a specific methodology (like Windows or TIA) to link cause and effect.

Courts generally reject global claims unless it is impossible to separate the events

www.deutschkerrigan.com

.

2. Ignoring Float Consumption

Analysts often argue that a delay is critical even if it consumed free float.

Avoidance: Understand the contract's definition of Float. If a delay consumes float but doesn't push the completion date, it may not be compensable

sccsinternational.org

.

3. Poor Logic in the Baseline

If the baseline schedule has "open ends," missing logic, or constraints that override logic, any analysis based on it is void.

Avoidance: Perform a "Schedule Health Check" (using DCMA 14-point assessment) before starting the analysis.

4. Hindsight Bias

In retrospective analysis, it is tempting to use information that wasn't known at the time.

Avoidance: Stick to the "Contemporaneous" view. What did the project team know at that moment? Windows Analysis helps prevent hindsight bias by locking the analysis to specific monthly periods

www.interface-consulting.com

.

The Role of Technology in Delay Analysis

Modern delay analysis relies heavily on specialized software.

Primavera P6: The industry standard for CPM scheduling. Its "Claim Digger" feature (though basic) allows for some comparison of schedules.

MS Project: Common in smaller projects, but less robust for forensic logic tracing.

Specialized Tools: Software like Trajectory or Forensic Schedule Analyzer plugins for P6 can automate the creation of windows and fragnets, reducing human error.

AI and Machine Learning: Emerging tools are beginning to use AI to scan thousands of emails and daily reports to automatically identify potential delay events and categorize them, speeding up the data collection phase

aven-ai.com

.

Case Study: The High-Rise Hotel Dispute

Note: This is a generalized illustrative case based on common forensic scenarios.

The Scenario:

A 40-story hotel project was planned for 24 months. It finished in 30 months (6 months late).

Contractor Claim: 6 months EOT + \$2M prolongation costs.

Employer Defense: 0 months EOT. Contractor was inefficient. Counterclaim for \$1.8M Liquidated Damages.

The Analysis (Windows Approach):

The forensic analyst divided the project into 24 monthly windows.

Months 1-6 (Foundation): The schedule showed a 2-month delay.

Cause: Unforeseen ground conditions (Client Risk).

Impact: Critical path delayed by 2 months.

Result: +2 Months EOT (Compensable).

Months 7-12 (Structure): The schedule showed a 1-month delay.

Cause: Contractor's crane broke down (Contractor Risk).

Cause: Client issued a change order for the lobby design (Client Risk).

Concurrency: Both happened in Month 9. The crane breakdown delayed the structure by 2 weeks. The design change delayed the fit-out by 3 weeks.

Analysis: The design change was on the critical path. The crane breakdown was on a near-critical path.

Result: +1 Month EOT (Compensable). The contractor cannot claim costs for the crane downtime because the design change would have delayed the project anyway? Actually, under SCL, if the Client Risk is dominant on the Critical Path, EOT is granted.

Months 13-24 (Fit-Out): The schedule showed a 3-month delay.

Cause: Slow manpower deployment by Contractor (Contractor Risk).

Impact: Critical path delayed by 3 months.

Result: 0 Months EOT (Non-Excusable).

The Outcome:

Total EOT: 3 Months (2 for ground conditions + 1 for design).

Financial: Contractor pays Liquidated Damages for the remaining 3 months of culpable delay.

Contractor receives costs for the 3 months of excusable delay.

Net Result: The claim was reduced from 6 months to 3 months, saving the Employer significant costs and ensuring the Contractor was fairly compensated for legitimate issues.

Conclusion: Precision, Protocol, and Proof

Delay analysis is not magic; it is a disciplined application of logic, contract law, and data science. It transforms a chaotic history of missed deadlines and finger-pointing into a structured narrative of cause and effect.

For the modern Project Manager and Planner, understanding these techniques is non-negotiable. Whether you are using Time Impact Analysis to forecast the future or Windows Analysis to dissect the past, the goal remains the same: to establish the truth of the project's timeline.

By adhering to the SCL Protocol, respecting the complexities of Concurrent Delays, and maintaining rigorous contemporaneous records, professionals can navigate the treacherous waters of project disputes. In the end, a well-substantiated delay analysis does more than just win claims—it preserves professional integrity and ensures that justice, in the form of time and money, is accurately served.

References & Further Reading

Society of Construction Law. (2017). Delay and Disruption Protocol.

www.scl.org.uk

Interface Consulting. (2023). Time Impact Analysis (TIA) Methodology.

www.interface-consulting.com

Long International. (2023). Concurrent Delay in Construction: Analysis & Legal Guide.

www.long-intl.com

MLR Project Management. (2024). Time Impact Analysis vs Window Analysis: Key Differences.

mlrprojectmanagement.com

AACE International. (2011). Forensic Schedule Analysis (Recommended Practice 29R-03).

PM World Library. (2023). Assessing Delay – the SCL Options.

pmworldlibrary.net

Calim AI. (2024). Delay Analysis Methods Explained: As-Planned vs As-Built.

www.calim.ai

HKA. (2023). Forensic Delay Analysis: Modeled or Planned v. As-Built.

www.hka.com

For more technical articles, training materials, and professional resources, visit our page in GitHub as a link below:

- <https://sbmousavices.github.io/industrial-Tools>

Copyright Notice: © 2026 Behzad Mousavi. All rights reserved. This article may be shared for educational purposes with proper attribution. Commercial use requires written permission from the author.